


SeaQuest Status June 23-29

Brian Tice
June 30, 2014





Previous Week






Detector Status - All systems performing well

- Drift chamber voltages adjusted (very slightly) to keep efficiencies high
 - The reason: Improved beam means increased intensity
- 6 noisy ASQD cards on drift chambers swapped during downtime on 6/26
- Surge suppressors installed on level shifter board and VME crates


- HV crate failed, was swapped
 - Problem from foam bits
 - Will be sent to PREP for repair






Beam Monitoring

- Introduced to AD ACNET variable FTSDF for seaquest duty factor
 - FTSDF— @53kHz (half-turn)
 - SQDUTY— @53MHz from SeaQuest Cerenkov





4

Beam Cerenkov Update

- Aging aluminized Kapton mirror was replaced with new aluminized Mylar mirror
 - Mirrors degrade from beam exposure
 - Change in material not significant. Important part is new mirror is not rad damaged.
- Change is to improve reliability and increase max intensity before saturation
- 10% neutral density filter was replaced with 5% filter
 - Reduces the signal to Cerenkov, lowering risk of saturation
- Cerenkov continues to scale reliably with G2SEM
 - Scaling rate of course is different
 - Duty factor calculation otherwise unaffected

Aging of mirror worse than expected, not understood





Other Updates

- Improved trigger firmware deployed
 - Acceptance of signal goes up
 - Acceptance of background goes down
- Tested running with 4 turn injections
 - Increasing from $3 \rightarrow 4$ turns increases intensity by ~1/3
 - 10 minutes of testing on 6/24 checked that beam and SeaQuest detector are OK
 - 1 hour of 4 turn data on 6/25 Enough to study intensity biases in trigger and analyses
 - Some signs of saturation in Cerenkov (this was before improvements on 6/26)
 - Expecting more 4 turn data this afternoon



SeaQuest AEM Update